

Test Summary No. 2

the FEMA Program to Reduce the Earthquake Hazards of Steel Moment Frame Structures

Specimen ID: EERC-PN2

Keywords: Pre-Northridge, simulated field welding,

panel zone yielding, weld fracture, small rotation capacity

Test Location: Earthquake Engineering Research Center, University of California at Berkeley

Test Date: March 14-15, 1995

Principal Investigator: Vitelmo V. Bertero; with Andrew S. Whittaker and Amir S. Gilani


Related Summaries: 15

Reference: "Experimental Investigations of Beam-Column Subassemblages," Report No. SAC 96-

01, March 1996.

Funding Source: FEMA / SAC Joint Venture, Phase I

CONNECTION DETAIL



MATERIAL PROPERTIES AND SPECIMEN DETAILS


Member	Size	Grade	Yield Stress (ksi)		Ultimate Strength (ksi)		
			mill certs.	coupon tests*	mill certs.	coupon tests*	
Beam	W30X99	A36	54.1	48.6 flange 57.4web	73.4	70.9 flange 72.9 web	
Column	W14X176	A572 Gr. 50	56.5	48.6 flange 53.5web	74.5	68.9 flange 70.8web	
Welding Procedure Specification Shear tab Panel zone Continuity plates	All welds FCAW-SS in conformance with AWSD1.1-94, performed with 0.120" diameter AWS E70T-4 electrodes. Preheat and interpass temperature per Table 4.3. Fillet weld of shear tab to beam web performed with 0.072" diameter AWS E71T-8 electrode. 1/2" × 4-1/2" × 23-5/8" plate with eight 7/8" A325 bolts No doubler plates 3/8" plates with CJP groove weld						
Boundary conditions	Single-sided test, no floor slab, axial load in lower half of column equal to shear in beam, specimen tested in upright position						
Other detailing	Connection between column and beam welded in the upright position						

*Coupon locations per ASTM

BACKGROUND

The objectives of testing the Pre-Northridge specimens were to replicate in the laboratory the failure modes observed in the field after the Northridge earthquake to develop a better understanding of the failure mechanisms, and to acquire data on the likely deformation characteristics of beam-column connections constructed to industry standards before 1994. The specimen described in this summary was fabricated under controlled conditions by a local commercial steel fabricator to details specified by SAC and the principal investigator. It was intended to be identical to the specimens described in Test Summaries No. 1 and 3. In addition, these were intended to be nearly identical to the specimens described in Test Summaries No. 4, 5, and 6 which were tested at U.C. San Diego. Because each of these were fabricated under controlled conditions, however, it is possible that their quality is superior to typical moment connections fabricated in the field prior to the Northridge earthquake. As such, some field-fabricated moment connections may exhibit less rotation capacity than these test specimens.

The standard SAC/ATC-24 loading history was used in the quasi-static testing of the specimen. The yield displacement (δ_{ν}) of the specimen was calculated from nonlinear analysis to be 1.40 in.



DISPLACEMENT HISTORY AND KEY EXPERIMENTAL OBSERVATIONS

Applied Displacement History	Key Observations of the Test		
$\delta = 1.4$ in. (analytical)	Point	Description	
3δ,	1	Shear yielding in the panel zone (displacement = $0.75 \delta_y$)	
$\begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} $	2	Fracture of welded connection of beam top flange to column flange	

DETAILED TEST RESULTS

Quantity (see Introduction for definitions used in EERC tests)				
	Peak actuator force (kips):	112		
Force/Displacement Properties	Beam deformation (in.):	1.6		
	Experimental yield displacement (in.)	1.1		
Detetion Conseits	Maximum plastic rotation (% radian):	1.1		
Rotation Capacity	Cumulative plastic rotation (% radian):	NA		
Energy Dissipation Properties Cumulative energy dissipated (k-in.):		438		

Mode of failure: Fracture of the welded beam top flange to column flange connection during the third $2\delta_{\nu}$ cycle.

DISCUSSION

Specimen EERC-PN2 failed during the first half-cycle of the third displacement excursion to $2\delta_y$. Failure of the groove welded connection of the beam top flange to the column flange occurred at a beam tip displacement of approximately -2.1 in. during this excursion. Failure of the specimen was preceded by shear yielding in the panel zone, first observed during the first displacement cycle to $0.75\delta_y$. The specimen failed abruptly during the $2\delta_y$ cycle. Visual inspection of the specimen following the testing suggest that there was little plastification in the beam. The maximum plastic rotation of the connection prior to failure was approximately 1.1% radian: 0.7% radian in the panel zone, and 0.4% radian in the beam. The panel zone dissipated substantially more energy than the beam.

DISCLAIMER

This summary has been prepared from the cited reference. The SAC Joint Venture has not verified any of the results presented herein, and no warranty is offered with regard to the results, findings, and recommendations presented, either by the Federal Emergency Management Agency, the SAC Joint Venture, the individual joint venture partners, their directors, members, or employees. These organizations and individuals do not assume any legal liability or responsibility for the accuracy, completeness, or usefulness of any of the information, products, or processes included in this publication. The reader is cautioned to carefully review the material presented herein. More detailed information is available in the cited reference.